V35014

INSTALLATION MANUAL - YARDMORE OVAL POOLS
POOL MODEL - REFLEXION



2.13

ABOVE GROUND POOL SAFETY
PLEASE READ BEFORE INSTALLATION

WARNING

FAILURE TO HEED THESE WARNINGS CAN RESULT IN PERMANENT INJURY, PARALYSIS FROM A BROKEN NECK, ELECTROCUTION OR DROWNING.
THIS POOL IS NOT DESIGNED FOR DIVING OR JUMPING!
DANGEROUS INJURY CAN RESULT, SHALLOW WATER!

Your pool contains a large quantity of water, and is deep enough to present inherent dangers to life and health unless the following safety rules are strictly observed. First-time users run the highest risk of injury. Make sure everyone understands. To insure your pool is used safely you must observe the following safety precautions:

1. NO JUMPING OR DIVING
The top rail of your pool is not a walkway and must not be used for jumping or diving. Do not permit jumping or diving into the pool from a deck or the top rail of the pool. Diving or jumping into the pool can result in serious injury.

2. NEVER USE THE POOL ALONE
Never permit the pool to be used unless it is attended by at least one person other than the bather. Someone should always be available to lend assistance in an emergency.

3. NEVER LEAVE CHILDREN UNATTENDED
Never leave a child alone and unsupervised in or near the pool—not even for a second. There is no substitute for constant adult supervision.

4. NO ROUGH PLAY
Do not permit "rough-playin" in and around your pool. Surfaces can become slippery and hazardous when wet.

5. LIGHT THE POOL AT NIGHT
If the pool is used after dusk, adequate lighting must be provided. Illumination in the pool area must be sufficient to clearly judge pool depth and all features in and around the pool. For lighting recommendations, consult your local licensed electrical contractor

6. RESTRICT ACCESS TO THE POOL
Do not leave chairs or other furniture beside the pool that could be used by a child to climb up into the pool. Ladders must be removed whenever the pool is unattended. A fence with a lockable gate around the pool or yard is strongly recommended and may be required by law in some jurisdictions.

7. NO ALCOHOL OR DRUGS
Never drink alcoholic beverages or use any intoxicants which could hinder your judgment and reflexes.

8. KEEP YOUR POOL CLEAN AND SANITARY
Your filter system will remove suspended particles from the water and the surface skimmer will remove insects, leaves and other debris from the water surface. Use the correct pool chemicals as directed to destroy harmful bacteria and prevent formation of algae. Remember, unsanitary water is a serious health hazard.

9. KEEP OFF TOP LEDGES
Do not walk on top ledges. They can be slippery and they are not a walkway.

10. POOL COVER SAFETY
The cover must have a tamperproof locking retainer cable that positions the cover around the pool wall and keeps it securely in place. Never allow anyone, especially small children on the cover. Asphyxiation or drowning could result. When purchasing any pool cover, please consult a swimming pool professional.

11. ELECTRICAL HAZARD
Never touch or attempt to service electrical equipment, including the filter when your body and/or the ground is wet. Electrocution or permanent injury due to high voltage (120V AC) could result. The pool should be bonded in accordance with Section 680-26 of the National Electical Code. For further assistance contact your dealer or a local licensed electrician. Do not use pool during electrical or rain storms.

12. SAFETY ROPE & POLE
Keep a safety rope 1/4" by 50" with a flotation buoy with an outside diamter of 15". Have accessible in a prominent area by your pool. Keep a pole not less that 16 feet (4,88m) long with a blunt or hook end available at pool side in case of emergencies.

13. POOL CHEMICALS
Do not place chlorine, chlorine tablets or sticks directly into skimmer, or winterize your pool with liquid chlorine. Damage to the skimmer, pool liner and filter will result. Failure to obey this instruction will void all component warranties. Always follow Chemical Manufacturer's instructions when storing, handling and dispensing pool chemicals.

14. CHECK FOR DAMAGE
Periodically check your pool and ladder components for damage and wear. Be sure all screws are in place. Replace all damaged or worn components and tighten all screws before you use the pool, deck or ladders. At first sign remove rust and touch up immediately.

15. POOL PARTS
Never modify the pool or accessories, or remove or drill holes in the pool, deck or ladder components unless instructed. Your pool wall is made of thin metal, there is an inherent cut hazard with metal so use gloves during installation. Always use Original Equipment Manufactured parts for your replacement parts.

FOLLOW ALL SAFETY INSTRUCTIONS
Read and follow all safety instructions packaged with pool, ladder, deck or any other accessory. Additional pool safety publications can be obtained by contacting: The Association of Pool & Spa Professionals (www.apsp.org)

REMEMBER
WATCH
CHILDREN

IMPORTANT NOTICE READ BEFORE INSTALLATION!

The safety stickers must be installed as per following instructions. Failure to properly install warning labels will void warranty. Failure to mount these safety labels may subject you to substantial liability in case of injury. These warning are not to be removed under any circumstances! If they become discolored or fall off please request replacements which will be sent at no charge.

PLACE SIGN ON LINER ABOVE WATER LINE, OPPOSITE ENTRY TO POOL

PLACE SIGN ON WALL NEXT TO POOL ENTRY

R.10/12

Section 1

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
GROUND PREPARATION

Read all instructions completely before you begin.

A. DETERMINE THE LOCATION OF YOUR POOL

1. The Terrain

Pay special attention to choosing the right location for your pool:
• Choose a large area, as flat and level as possible and well drained. ***(Image 1)***

• Choose a spot on dry, firm earth (stabilizer or other)—do not install the pool on asphalt, tar or oil based surfaces, gravel, peat moss, wood or chemically treated soil.

• Check with your pool dealer to see if Nut Grass grows in your area. This type of grass may grow up through your pool liner. Your dealer will be able to advise how best to treat the site.

• Sloped areas will need to be made level by digging away high spots, not by filling low spots—be prepared to hire earth-moving equipment if necessary.
(Images 2a & 2b)

• Ensure the earth is well compacted and a wall is placed to prevent the earth from seeping out.
(Image 2a)

• If you need to install partly in the ground, you must contact your dealer to see if this is an option for you and that you meet law requirements in your jurisdiction. ***(Image 2c)***









Important Note:
Ground preparation is one of the most important steps in the installation process. A proper foundation will ensure the rest of the pool assembly goes smoothly and that no problems will occur when the pool is filled with water.

Section 1

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
GROUND PREPARATION

A. CONT. DETERMINE THE LOCATION OF YOUR POOL

2. Things to Avoid

Do not locate your pool near or on any of the following ***(Images 3a to 3c)***:

• Overhanging tree branches.

• Overhead wires and clotheslines.

• Buried pipes and wires. Contact your gas, electric and telephone utilities to find buried pipes and wires before you dig.

• Areas with poor drainage.

• Grass, stones and roots. Grass will rot underneath the pool liner, and stones and roots will damage the pool liner.

• Areas recently treated with oil-based weed killers, chemicals or fertilizers.



3. Plan Ahead

• Will you be adding an adjacent deck later? Be sure to leave room.

• Will you be using pool accessories or other appliances that need electricity or gas? Locate your pool near these services or plan to have them installed later by a licensed contractor.



Important Note:
When locating the centre of the pool, be sure to take into consideration any structures (deck, patio, house) or relevant items (change rooms, gazebo, etc.) that the pool may need to line up with and ensure that the pool is in the most visual pleasing location for your property.



Section 1

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
GROUND PREPARATION

A. CONT. DETERMINE THE LOCATION OF YOUR POOL

4. Tools Needed

List of required materials

- Straight wood plank
- Material that provides a permanent base (ex. Crushed stone)
- Fine sand (void of debris)
- Cement blocks (5cm x 20cm x 40cm / 2"x 8"x16") (optional)
- 2x Plywood (60cm x 120cm /2ft x 4ft)
- Wood board (30cm x 20cm / 1ft x 1ft)
- Vinyl covered hooks (to hold wall steady)
- String and stakes & wooden pegs
- Prefabricated cove sections (optional)
- Pool carpeting (optional)
- Rope
- Polyethlyne Plastic Sheeting

- Optical Level
Can be useful for precise measurements

Section 1

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
GROUND PREPARATION

PARTS LISTING - EXPLODED VIEW

Reflexion RRR
PREF-YM54RRDRRRS11
Yardmore
Round Section

> **Important Note:**
> Make sure you have all the parts necessary before you start installation.



GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
GROUND PREPARATION

PARTS LISTING - EXPLODED VIEW

Reflexion RRR
PREF-YM54RRDRRRS11
Yardmore
Straight Section



Section 1

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
GROUND PREPARATION

PARTS LISTING - CONTENTS

Product Description :	Reflexion Oval								Revised Sept. 2012
Product Code:	PREF-YM54RRDRRRS11								
				Quantity required for installation (by pool size)					
Index#	Description	Part #	Length	1526	1530	1833	1840	1844	2143
A	Stabilizer 15', 18'	10715071600000		8	8	10	10	10	
A	Stabilizer 21'	10724071600000							10
B	Bottom Rail (Round section) 15'	10815021600000		8	8				
B	Bottom Rail (Round section) 18'	10818021600000				10	10	10	
B	Bottom Rail (Round section)21'	10821021600000							10
C	Stabilizer (Straight side section)	10702000042		4	6	6	10	12	12
D	Stabilizer transition (End of straight side section) 15 pi, 18 pi	10715071600010		4	4	4	4	4	
D	Stabilizer transition*(End of straight side section)21 pi	10724071600010							4
E	Bottom Rail (Straight side section)	10802000042		4	6	6	10	12	12
F	Bottom Rail transition (End of straight section) 15' Right	10815021600040		2	2				
F	Bottom Rail transition (End of straight section)15' Left	10815021600050		2	2				
F	Bottom Rail transition (End of straight section) 18' Right	10818021600040				2	2		
F	Bottom Rail transition (End of straight section)18' Left	10818021600050				2	2	2	
F	Bottom Rail transition (End of straight section) 21' Right	10821021600040							2
F	Bottom Rail transition (End of straight section) 21' Left	10821021600050							2
H	Steel wall (hole-to-hole)			1	1	1	1	1	1
	Steel bar	11825		2	2	2	2	2	2
I	Vinyl liner (hook)			1	1	1	1	1	1
I	Vinyl liner (overlap)			1	1	1	1	1	1
K	Upright 54"	10202160004		10	10	12	12	12	12
L	Top ledge	10102160000	56"	12	12	14	14	14	14
M	Ledge cover (back)	10302160000		16	18	20	24	26	26
N	Decorative bottom plate	10402160000		10	10	12	12	12	12
O	Soft ledge cover	10607160000		16	18	20	24	26	26
P	Stainless screw 12 x 1"	2PPS121		96	108	120	144	156	156
Q	Top Ledge (straight)	10102160042	42"	4	6	6	10	12	12
R	Upright cover 54"	10202000004		6	8	8	12	14	14
S	Aqua Leader logo (54' only)	13002000010		6	8	8	12	14	14
T	Rigid Ledge Cover (straight side section)	10302160010		6	8	8	12	14	14
U	Steel pressure plate	16549		6	8	8	12	14	14
V	Steel strap end channel	16539		6	8	8	12	14	14
W	Under channel	15933		6	8	8	12	14	14
X	Straps 15'	16725		9	12				
X	Straps 18'	16726				12	18	21	
X	Straps 21'	22126							28
Y	Washer 3 holes	16663		12	16	16	24	28	28
Z	Straight side steel upright 54"	22151		6	8	8	12	14	14
AA	Right gusset	16375		6	8	8	12	14	14
AA	Left gusset	16374		6	8	8	12	14	14
BB	Metal top plate	10136R		6	8	8	12	14	14
CC	Resin top plate	10433160010		6	8	8	12	14	14
DD	Resin bottom plate straight section	10402000000		6	8	8	12	14	14

Section 1

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
GROUND PREPARATION

PARTS LISTING - CONTENTS

Product Description :	Reflexion Oval								Revised Sept. 2012
Product Code:	PREF-YM54RRDRRRS11								
				Quantity required for installation (by pool size)					
Index#	Description	Part #	Length	1526	1530	1833	1840	1844	2143
EE	Bolt 5" x 5/16 - 18	99-0073		36	48	48	72	84	84
FF	Bolt 4 ½" x 5/16 - 18	99-0045		12	16	16	24	28	24
GG	Nut 5/16 - 18	99-0027		72	96	96	144	164	178
HH	Screw ½" x 5/16 – 18	99-0026		24	32	32	48	56	70
II	Screw ½" #10	99-0068		42	56	56	84	98	98
JJ	Screw ¾" #12 truss head	99-0022		30	42	42	66	78	78
KK	Screw 1" #10	99-0070		24	32	32	48	56	56
LL	Bolt 5 ½" x ¼ - 20	2PCB520		6	8	8	12	14	14
MM	Nut ¼ - 20	2PNS109		6	8	8	12	14	14
	Hardware	1051526160		1					
	Hardware	1051530160			1				
	Hardware	1051833160				1			
	Hardware	1051840160					1		
	Hardware	1051844160						1	
	Hardware	1052143160							1
	Oval channel end cap	22726		6	8	8	12	14	14
	Installation DVD	36875		1	1	1	1	1	1

Section 1

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
GROUND PREPARATION

B. PREPARE THE FOUNDATION OF YOUR POOL

1. Mark out the Area

a. The next following steps will show you how to mark out the area you need for the oval pool. This marked area will be larger than the pool size itself, but this space is needed. Find a site where the ground is stable, level and well drained. Once you have selected your site, determine where the middle of your pool will be.

See Diagrams:
Please see pg 18 for an example on how to correctly mark your pool area. Please verify your pool's footprint for correct measurements on the last pages of this Section 1.

b. Drive a peg into the ground at the centre point. ***(Image 1)***

c. Once the center has been established, you must now determine the outer limits of the perimeter of your pool. Add 12" (30 cm) inside this measurement to determine pool perimeter. ***(Image 2)***

d. Now you must make the round ends that will be the oval part. In order to do so, you will have to determine the center of the radius on each side and drive a peg into the ground. ***(Image 3)***

e. Using a length of string tied between the peg and a can of spray paint mark the circles on the ground. ***(Image 4)***



1



2



3



4

Section 1

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
GROUND PREPARATION

B. CONT. PREPARE THE FOUNDATION OF YOUR POOL

f. Mark areas along both straight sides of your oval. Use pegs and string as a guide for the can of spray paint to mark straight lines. ***(Image 5)***



5

g. You now have the space marked out that is needed for your oval pool. ***(Image 6)***



6

2. Remove the sod

a. Remove the sod from the area you have just outlined. ***(Image 7)***

b. Remove all debris (rocks, roots, etc) using a rake. Then compact the ground to achieve a firm base.



7

Important Note:
Your pool must be perfectly level. Take the time you need to be sure your foundation is perfecty level.

Section 1

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
GROUND PREPARATION

B. CONT. PREPARE THE FOUNDATION OF YOUR POOL

Example on how to mark out pool area for an 18 x 33

Please be sure to use your pool's footprint for your pool size on the last pages of this Section1.



Perimeter 1047" (hole to hole)-Track length measured in track slot
All dimensions are in inches

Section 1

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
GROUND PREPARATION

B. CONT. PREPARE THE FOUNDATION OF YOUR POOL

3. Make the area flat and level

a. Remove all the high spots with a shovel, hoe or rake. To make sure your pool is stable, compact the ground well before adding the sand. Be prepared to hire earth moving equipment if you need to level a large area. Remember, your pool must be level across the diameter of the pool. ***(Image 8)***


8

b. Small dips and hollows may be filled in, but the soil must be hard-packed with a tamping tool.

c. Take material such as rock dust or fine mortar that can conform a solid, permanent base and deposit this material around the rim of the basin. ***(Image 9)***


9

d. The material used should be spread around the perimeter of the pool to a width of 24" (60cm) and a thickness of 2" (5cm). ***(image 9a)***

e. Recheck the outer perimeter of the oval shape, where the pool wall will be placed. Compact the ground and make sure there are no high or low spots. The bottom edge of the pool wall must rest flat on the ground and have no gaps under it.



9a

Helpful Hint:
Use the optical level to ensure that the ground is perfectly flat and level.

Important Note:
Your pool must be perfectly level. Take the time you need to be sure your foundation is perfectly level.

Section 1

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
GROUND PREPARATION

C. PRE-ASSEMBLY OF THE STRAIGHT SECTION

1. Assembling the strap end channel

a. Overlay the strap en channel over the underbox channel (under box channel is belly-up). ***(Image 10)***

b. Align the holes of the strap end channel with those of the underbox channel, but do not secure them with the bolts at this time. ***(Image 11)***



c. Slide the steel upright over the strap end channel making sure that the holes line up. The steel upright opening must face the longest part of the strap end channel. ***(Image 12)***



GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
GROUND PREPARATION

C. CONT. PRE-ASSEMBLY OF THE STRAIGHT SECTION

d. Insert the left and right gussets. the pieces are marked "L" and "R". Ensure that the holes are aligned. Slide the steel upright over the strap end channel. ***(Image 13)***

e. All holes should be lined up at this point. Use the 5/16" x 5" bolts and 5/16" nuts for the channels and the 5/16" x 4 1/2" stainless steel bolts for connecting the gussets to the steel uprights. **Remember to include the three-hole washers on the front side of the gussets.** ***(Images 14 & 15)***



Section 1

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
GROUND PREPARATION

C. CONT. PRE-ASSEMBLY OF THE STRAIGHT SECTION

f. Once these pieces are in place, screw the left and right gussets to each other using three #10 screws. ***(Image 16)***

g. In order to ensure that the steel upright and the channels are at right angles during the assembly, push the ends of the steel upright and the channels and tighten the bolts at the same time. First, tighten the bolts of the channels by maintaining a good pressure. For the screws on the steel upright and gussets, sufficiently tighten the bolts to let the screws exceed 1/8". ***(Images 17 & 18)***



Section 1

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
GROUND PREPARATION

C. CONT. PRE-ASSEMBLY OF THE STRAIGHT SECTION

h. Place a steel top plate on the top of each of the pool steel structures. The holes of the steel top plate and steel structure must be aligned and screwed on the side using a #10 screw.



19

i. Before bolting the strap sections to the strap end channels, add these end channel caps with foam blocks to the underside of the straps at each end.

j. Insert the foam block in the front part of the strap end channel, insert it at least 1 1/2" past the edge of the channel. ***(Image 20)***



20

Section 1

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
GROUND PREPARATION

C. CONT. PRE-ASSEMBLY OF THE STRAIGHT SECTION

k. Slide a strap under the front part of a channel, the two holes in these End Channel Caps will line up with the two holes in the straps, as well as, the corresponding holes in the strap end channels themselves. ***(Image 21)***



21

END CHANNEL CAPS

l. The End Channel Caps are secured in place using the same two 5/16" x 1/2" bolts and 5/16" nuts that are used to secure the straps to the strap end channels. ***(Images 21 & 22)***



22

Helpful Hint:
Do not be alarmed if you are not using all of the holes in the strap end channels.

Section 1

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
GROUND PREPARATION

D. GROUND PREPARATION FOR THE BUTTRESS

1. Measuring for the buttress trenches

a. In order to measure where trenches need to be dug for the placement of the buttress, you must first draw a perpendicular line in order to create a perfect 90 degree angle. From the pool center, trace a straight line to the oval perimeter. ***(Image 13)***



13

b. In order to ensure that your line is perpendicular, measure from each radius center to the top of your line. The measurement should be exactly the same on each side. If not, adjust until both are the same and you will now have a perfect perpendicular line, therfore creating a perfect 90 degree angle. ***(Images 14 & 15)***



14

c. Repeat the first two steps to create a perpendicular line in order to create a perfect 90 degree angle for the other side of the oval pool.



15

Important Note:
It is very important that when you follow the instructions on the next page, that you apply the next steps to only one side of the pool at a time. It is imperative that you follow the next steps in order.

Section 1

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
GROUND PREPARATION

D. CONT. GROUND PREPARATION FOR THE BUTTRESS

2. Digging the buttress trenches

Odd number of trenches;

a. If your oval pool contains an even number of buttresses, please proceed with next step. If your oval pool contains an odd number, position the buttress temporarily on the straight center line from the middle. ***(Image 16)***

b. Trace around the buttress and dig a trench. Dig the trench 3 to 5 inches deep by 10 inches wide and the length of 52 1/2 inches long. ***(Image 17)***

c. The bottom plates for the straight section must be at the same level with the crushed stone. If you do not put crushed stone, understand that the bottom plates all around the pool must be at the same level. The warranty will void if you do not comply with this requirement.

d. Apply crushed stone at 1 inch, then compress. Place a concrete block of 2 inches at each end of the trench.

Important Note:
This first buttress that you install will be the reference to install the remaining butresses, therefore ensure that measurments and placements are exactly where they need to be.

e. Once the block is installed, measure the depth of the trench, it must be 2 inches deep. Make sure the block is level by using an optical level. Ensure that both blocks are at the same level.

f. Place the buttress structure on the blocks and ensure that each buttress is parallel to each other. ***(Image 18)***



16

17

18

Section 1

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
GROUND PREPARATION

D. CONT. GROUND PREPARATION FOR THE BUTTRESS

Even number of buttresses:

a. If your oval pool contains an even number of buttresses, measure from the center line out 21". Position the buttress temporarily off the straight center line from the middle. ***(Image 19)***

b. Trace around the buttress and dig a trench. Dig the trench 3 to 5 inches deep by 10 inches wide and the length of 52 1/2 inches long. ***(Image 20)***

c. The bottom plates for the straight section must be at the same level with the crushed stone. If you do not put crushed stone, understand that the bottom plates all around the pool must be at the same level. The warranty will void if you do not comply with this requirement.

d. Apply crushed stone at 1 inch, then compress. Place a concrete block of 2 inches at each end of the trench.

Important Note:
This first buttress that you install will be the reference to install the remaining buttresses, therefore ensure that measurments and placements are exactly where they need to be.

e. Once the block is installed, measure the depth of the trench, it must be 2 inches deep. Make sure the block is level by using an optical level. Ensure that both blocks are at the same level.

f. Place the buttress structure on the blocks and ensure that each buttress is parallel to each other. ***(Image 21)***



19

20

21

Section 1

GENERAL INSTRUCTIONS - BRACELESS OVAL POOLS
GROUND PREPARATION

D. CONT. GROUND PREPARATION FOR THE BUTTRESS

4. Finish trenches & patio stone installation

a. Continue to finish one by one the remaining trenches with patio blocks for the buttress installation. **It is important to finish one side of the oval only.**

b. Once all the trenches are dug and buttresses with patio stones are installed, **on the one side only.** Remeasure each buttress to ensure that they are all straight and that the buttress is perpendicular. ***(Image 22)***

d. From the first buttress, check to see that second buttress is 45" from center and continue to ensure that all measurements between each buttress is equal.

e. *Now add crushed stone around the buttress (do not cover) and be careful not to move the buttress. Take measurements at every upright and then check measurement again. ***(Image 23)***



***Important Note when installing second side:**
As soon as you are done installing the second side of the buttresses, measure the two intersecting axes FIRST before adding crushed stone.
Ensure that the two straight sections are parallel. If they are not, you **MUST** rectify.
Once all is perfectly parallet, you may add crushed stone and continue with assembling straps and pressure plates on the remainging side.



Section 1

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
GROUND PREPARATION

E. ASSEMBLING THE BUTTRESS STRAPS AND PRESSURE PLATES

1. Assemble the buttress straps and brace

a. Place crushed stone or soil where the pressure plates are located. This will have the effect of supporting the pressure plate.

b. Put pressure plates on the tip of the strap end channel to 20 1/2" from the steel upright. The side that is corrugated must be facing up and the flat side facing the ground. ***(Images 24 & 25)***

c. For the alignment of the pressure plate there is a hole at less than one inch from the edge of the plate. This hole is facing the vertical part of the steel structure. Once the plates are in position, secure them to the channels using two #12 x 3/4" screws. ***(Image 26)***

d. Once all plates are secured to the channels, the plates should overlap each other. Secure the plates to each other using three #12 screws in each overlapping area.

e. You may now go back to step 2-Digging the buttress trenches, to continue for the remaining side of the oval.



24



25

26

Important Note:
If the holes do not align, DO NOT drill holes! Verify the alignment of the structures.

Section 1

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
GROUND PREPARATION

E. ASSEMBLING THE BUTTRESS STRAPS AND PRESSURE PLATES

f. Once both sides of the buttresses have been installed perfectly, check that all is measured perfectly.

g. Add the remaining straps that join across to other straps. Make sure the screw heads are facing upward. Remeasure and tighten screws. Recheck measurement again. ***(Images 25 & 26)***



25

Important Note:
Ensure that the straps raise higher in the middle, therefore you may need to put a little more stone dust underneath, appx 1/2".



26

h. Measure the two intersecting axes to ensure that the two straight sections are parallel. ***(Image 27)***



27

Note:
It may feel tedious to be always measuring, but this only helps to ensure proper installation and avoiding problems further on.

2. Proceed to Section 2 - Assembling the Pool Base

Section 1

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
GROUND PREPARATION

OVAL FOOTPRINT - 12 x 24



Section 1

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
GROUND PREPARATION

OVAL FOOTPRINT - 15 x 26



Section 1

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
GROUND PREPARATION

OVAL FOOTPRINT - 15 X 30



Section 1

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
GROUND PREPARATION

OVAL FOOTPRINT - 18 X 33



Section 1

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
GROUND PREPARATION

OVAL FOOTPRINT - 18 X 40



Section 1

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
GROUND PREPARATION

OVAL FOOTPRINT - 21 x 43


4x Transition bottom track left and right Ø21' (54")
4x Transition stabilizer 24' (53.75")
42'-0"
10x Bottom Track Ø21' (56")
10x Stabilizer 24' (55.875")
Gap between bottom tracks 0.698"
R 10' 7"
21'-1 1/2"
29'-9 1/2"
20'-10 1/2"
3'-6"
4'-1"
28 places
12x Straight side track Ø15' (37")
12x Straight stabilizer 15' (37.25")
Perimeter 1300" (hole to hole) -Track length measured in track slot -All dimensions are in inches

Section 2

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
ASSEMBLING THE POOL BASE

A. INSTALLATION OF BOTTOM PLATES AND BOTTOM RAILS

1. Bottom plates & rails - straight section

a. Screw the bottom plate on the strap end channel. The bottom plate has to sit on the edge of the strap end channel and the steel upright. ***(Images 1 & 2)***

b. Remove dust and dirt between the bottom plate and the strap end channel.

c. Install the straight bottom rail between the steel structures. The bottom rail has to fit inside the bottom plate, remove any dirt or small rocks during installation. ***(Image 3)***

d. install the end of the straight bottom rail between the straight and the round sections of the pool.

1

Bottom plate



2

Important Note:

There are three types of bottom rails. Bottom rails for the straight section, bottom rails for the round section and bottom rails for the end of the straight section (Transition).

To differentiate which bottom rail is which;
Straight Section: will measure 42" in length
Transition Section: will measure appx. 53" in length
Round Section: will be the longest measure

See Diagrams:
Please refer to your pool's footprint (Section 1, last pages) for gap measurement,

3

Section 2

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
ASSEMBLING THE POOL BASE

A. INSTALLATION OF BOTTOM PLATES AND BOTTOM RAILS

2. Bottom plates & rails - round section

a. Continue the installation of the bottom plates of the round sections. Insert the end of each bottom rail into the bottom plate. Leave a gap between the ends of the bottom rails. ***(Images 4 & 5)***

4

⚠ Important Note:

There are three types of bottom rails. Bottom rails for the straight section, bottom rails for the round section and bottom rails for the end of the straight section (Transition).

To differentiate which bottom rail is which;
Straight Section: will measure 42" in length
Transition Section: will measure appx. 53" in length
Round Section: will be the longest measure



5

See Diagrams:
Please refer to your pool's footprint (Section 1, last pages) for gap measurement,

Section 2

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
ASSEMBLING THE POOL BASE

A. CONT. INSTALLATION OF BOTTOM PLATES AND BOTTOM RAILS

3. Patio Stones (Optional)

Contact your Dealer:
Please contact your dealer for more information about using patio stones.

a. Concrete patio stones may be placed at the base of each upright of your pool. ***(Image 6)***

b. Each bottom plate will show the location for a patio stone. Make a mark in the ground at each base plate.

c. Remove the bottom rails and bottom plates and lay out the patio stones around the circle where the bottom plates were.

d. The patio stones must be sunk into the ground so the tops are flush with the soil around them. **Use the carpenter's level to make sure the patio stones are perfectly level and flush with the ground.** Use either the carpenter's level and a 2-by-4 (5cm x 10cm) wood plank, or the optical level between patio stones to make sure the stones are level with each other. ***(Image 7)***

e. Do not install blocks or rails on loose sifted soil or sand. There must be no space between the ground and the bottom of the rails. All patio blocks must be flush with the ground, solid and level with each other in all directions.

NOTE: Installing patio blocks is optional and the blocks may shift due to temperature changes.





Contact your Dealer:
Please contact your dealer for more information about using patio stones.

Important Note:
Make sure the patio stones are perfectly level and flush with the ground. All patio blocks must be flush with the ground, solid and level with each other in all directions.

Section 2

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
ASSEMBLING THE POOL BASE

A. CONT. INSTALLATION OF OF BOTTOM PLATES AND BOTTOM RAILS

4. Measure the perimeter of your pool

a. Measure the perimeter of your pool and hammer nails into the ground to keep the bottom rails into place. These nails are to be removed only at the last step-when filling up the pool. ***(Image 8)***


8

Important Note:
Use a soft measuring tape to meaure around the perimeter of the pool. Measure from the inside of the bottom rail, the measurement should equal the wall length.

b. Verify the height of each bottom plate with an optical level. Ensure that they are the same height.

5. Fill inside the pool area

a. Pour sifted sand in the centre of your pool. Ensure that you will have enough to spread approximately 2" (2.5cm) around the inside pool area. ***(Image 9)***

9

b. Spread the sand inside the pool area. Make sure not to spread the sand onto or beyond the bottom rails. Compact the sand manually or mechanically.

Section 2

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
ASSEMBLING THE POOL BASE

B. INSTALL UPRIGHTS FOR STRAIGHT SECTION

1. Installation of uprights - straight section

a. Fix the upright cover over the buttress. ***(Image 10)***

b. Attach the bottom of cover with 1/4 inch xx 5/12 inch bolts. ***(Image 11)***

(You will insert the uprights for the round section after the wall installation).



10

2. Proceed to Section 3 - Assembling the Pool Wall

11

Section 3

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
ASSEMBLING THE POOL WALL

A. SETTING UP THE POOL WALL

Do not attempt to install the pool wall in the wind, wait for a calm day.
It takes at least 3 people to install the pool wall.

1. Preparing for the wall installation

a. Bring the following items into the middle of the pool foundation before you start uncoiling the pool wall: plywood, some extra sand or fine dirt to make the cove and a ladder to climb out after the wall is assembled.

b. Make sure the skimmer and water return holes are located where you need them to be. The skimmer and water return holes are positioned towards the end of the wall, **(the section before where the wall started)**.


1

2. Set the pool wall in place.

a. Unpackage the coiled pool wall and stand it on the plywood at the place close to where you need to install the skimmer. ***(Image 1)***
(Remember the skimmer and water return holes will be placed at the section just before where you started the wall installation).

b. Start uncoiling the wall, guiding the bottom edge into the curved bottom rail. The starting end of the wall must be positioned in the centre of a bottom plate, and the skimmer and return holes should be positioned where the pump and filter will be. ***(Image 2)***

2

c. As you erect the wall, install the stabilizers temporarily to obtain greater stability. You should also use heavy vinyl-covered hooks and rope to hold the wall steady. Ideally, however, you should work with several people. ***(Image 3)***

d. When uncoiling the wall, the skimmer and return holes are positioned toward the end of the wall.

3

⚠ **Important Note:**
It is preferable to use very fine sand that is easily compacted. Be careful not to spill sand on the bottom rails.

Section 3

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
ASSEMBLING THE POOL WALL

A. CONT. SETTING UP THE POOL WALL

3. Join the ends of the pool wall

a. Line up the holes in the two ends of the pool wall. ***(Image 4)***

b. Now that you have installed the wall you can be faced with three scenarios.

1) The wall joints align perfectly, if so, move on to the next step (c).

2) Your wall appears to be too short. **It is not.** However the space between the bottom rails must be decreased by lightly tapping the bottom plates towards the inside of the pool. You can also tap the wall lightly with both hands in the desired direction. ***(Image 5)***

You MUST recheck the gaps at each and every one of the bottom rails so that they are all equal in gap size.

3) Your wall appears too long. **It is not.** However the space between the bottom rails must be increased by tapping the bottom plates lightly towards the outside of the pool or by tapping the wall with both hands in the desired direction. ***(Image 6)***

You MUST recheck the gaps at each and every one of the bottom rails so that they are all equal in gap size.



4


5


6

Important Note:
Bottom rails must always be held in place in the bottom plate.

Important Note:
You MUST recheck the gaps at each and every one of the bottom rails so that they are all equal in gap size.

c. Recheck the position of the upright, refer to your pool's footprint diagram.

Section 3

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
ASSEMBLING THE POOL WALL

A. CONT. SETTING UP THE POOL WALL

d. To fasten the wall joint, overlap the two steel bars, one on the inside and the other on the outside. Tighten the mechanical screws on the inside and the nuts on the outside. Ensure that all bolts and all the holes are used. ***(Image 7)***



7

Important Note:
Stick a screwdriver through two of the holes to help line up the ends of the wall.

When tightening the screws start from either the top and go down or vice versa. Do not start a few screws from top and a few from the bottom to meet in the middle, this can cause problems later on.

e. Adjusting the pool to the proper shape may cause the bottom rails and bottom plates to slip out of alignment a little. Recheck all of the bottom plates to make sure each one is centred where the bottom rails meet.



8

f. Cover the seam and bolt heads on the inside/ interior of the pool wall completely with 2" (50mm) duct tape. ***(Image 8)***

Important Note:
The pool must be level across the perimeter. A pool that is not level is dangerous and may collapse.

Section 3

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
ASSEMBLING THE POOL WALL

B. ASSEMBLING THE COVE

1. Make the cove

a. If you are using sand, bank the sand against the wall to form a cove of 3" to 6" (7.5cm to 15cm) high and 8" to 12" (20cm to 30cm) wide at ground level. This will prevent the liner from creeping under the wall, and it will also protect the liner from any metal edges of the pool framework. THIS STEP IS NOT OPTIONAL, IT MUST BE DONE. ***(Image 9)***



9

b. Water the sand to compact it and use a trowel to spread it evenly. ***(Image 10)***

10

c. Since earth containing chemicals can cause discoloration or corrosion, it is suggested that you place **polyethylene plastic sheeting** under the cove around the perimeter of the wall, so no earth comes in contact with the metal. Since the presence of such chemicals is beyond the control of the manufacturer, such damage is not covered under warranty. ***(Image 11)***

d. If you are using styrofoam cove pieces instead of sand, insert them in the bottom rail and refer to the installation instructions that are provided with them.



11

Important Note:
The cove is an important part of the pool structure. Take your time to make a complete, full-size cove.

Section 3

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
ASSEMBLING THE POOL WALL

B. CONT. ASSEMBLING THE COVE

e. A vacuum cleaner can later be used to remove the air from between the liner and the wall. This technique enables you to remove folds in the liner. However the following precautions should be taken:

Do not use an industrial vacuum cleaner which could be too powerful.
Tape the end of the vacuum hose before inserting it into the wall so as not to damage the liner.
Insert the nozzle until it is about 4" (10cm) above the cove (insert through the water return outlet or the skimmer depending on the diameter of your hose). Make sure you will be able to remove the hose later on.
Tape the hose to the wall. ***(Image 12)***

f. Close the skimmer opening with cardboard and adhesive tape so that the suction of air works better. ***(Image 13)***

Section 3

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
ASSEMBLING THE POOL WALL

C. INSTALL THE POOL LINER

1. Set the liner in place

a. Open the carton. Do not use anything sharp to open the carton.

b. Unpack and unfold the liner and spread it out in the sun to warm it up. Inspect all the seams and surfaces for holes.

c. Remove your shoes to avoid damaging the base or tearing the liner.

d. Spread out the liner, smooth side down. Unfold the liner from the centre of the pool toward the sides. ***(Image 14)***

e. Use the liner's bottom seam(s) as a guide and make sure the seam(s) are parallel to the straight sections and to the imaginaryl ine which links points A and B in the illustration ***(Image 15)***. It is recommended that you begin installing the liner in a round section.

f. Use the liner's vertical seam as a guide and make sure the seam is vertical and perpendicular to the wall and bottom.

g. Make sure the seam between the wall and bottom is centred on the cove ***(Image 16)***

h. Smooth out all the wrinkles in the bottom. Do not leave any space between the liner and cove.



14



15



16

Important Note:
If possible, unfold the liner on the grass one to two hours before installation. Be careful not to leave the liner too long or you may damage the grass.

Important Note:
The liner is generally smaller than the support structure of the pool. It will stretch more easily when warm. It is important that the liner is installed on a warm sunny day.

Section 3

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
ASSEMBLING THE POOL WALL

C. CONT. INSTALL THE POOL LINER

Please ensure to follow instructions that match the type of liner you may have.

2. Fasten the liner place (OVERLAP ONLY)

a. Starting at the liner wall seam, hang the liner over the wall making sure that the seam is straight up and down, perpendicular to the floor. (Remove stabilizers gradually as you fold the liner over the top of the wall.)This will assure you that the liner begins going over the wall straight. ***(Image 17)***


17

b. As you put the liner over the wall you can secure it by using the plastic coping strips to keep it in place. If you end up with excess material, continue around the pool, pulling excess liner evenly, and distribute over the wall until the excess is gone. ***(Image18)***

c. Fasten the liner to the top of the wall with plastic coping. Let the liner hang slack for now. Do not pull the liner tight. ***(Image 18)***



18

NOTE: Some liners may fit very tightly, it is better to install uprights, top plate and rail before going onto next step. See Section 4.

d. Turn the vacuum cleaner on and push the liner outward with your feet to iron out any wrinkles. Once finished, turn off vacuum cleaner.

e. Start filling the pool with water. As the pool fills, work out all the wrinkles and smooth the liner to the wall. Remove the plastic coping around the top edge of the wall one piece at a time and adjust the liner. Keep smoothing out the wrinkles.

Important Note:
Do not trim off the excess liner. (If the liner ever needs to be removed, trimming the liner will make re-installation very difficult.) Instead, roll up any excess liner and tape it in place near the top of the pool wall.

Section 3

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
ASSEMBLING THE POOL WALL

C. CONT. INSTALL THE POOL LINER

f. After all the wrinkles in the liner are removed, trim any extra length of plastic coping so there is no overlap. ***(Image 19)***

g. Roll up any excess liner hanging below the plastic coping and tape it in place near the top of the pool wall. Important: Do not trim off the excess liner. ***(Image 20)***



Important Note:
Do not trim off the excess liner. (If the liner ever needs to be removed, trimming the liner will make re-installation very difficult.) Instead, roll up any excess liner and tape it in place near the top of the pool wall.



Section 3

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
ASSEMBLING THE POOL WALL

C. CONT. INSTALL THE POOL LINER

4. Fasten the liner in place (HUNG/J or V-BEAD LINER ONLY)

a. With a V-Bead liner you will not use the plastic coping strips that are packed in the parts carton of your pool. You can discard those pieces, if they are included, as they only apply to pools with overlap liners.

b. The top of the wall of the liner has what is called a "V-Bead" welded onto it. Simply open up the bead with your fingers and hang it directly on top of the pool wall. When this is done properly, the only portion on the outside of the pool wall is approximately 1" of the V-Bead. No printed liner material is actually going over the top of the wall to the outside of the wall. ***(Image 21)***

c. Make sure the bead is on evenly around the entire pool, and that the liner is hanging straight down from the top of the wall. The liner should not have creases in it because it is twisting around the pool. If the liner is twisting, it is because it is not sitting properly in the pool. Make necessary adjustments before proceeding.



21

NOTE: Some liners may fit very tightly, it is better to install uprights, top plate and rail before going onto next step. See Section 4.

Important Note:
Do not trim off the excess liner. (If the liner ever needs to be removed, trimming the liner will make re-installation very difficult.) Instead, roll up any excess liner and tape it in place near the top of the pool wall.

Section 3

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
ASSEMBLING THE POOL WALL

C. CONT. INSTALL THE POOL LINER

3. Fasten the liner place (BEADLOCK/SNAPBEAD LINER ONLY)

a. With a snap bead liner you will not use the plastic coping strips that are packed in the parts carton of many pools. You can discard those pieces (if they are included). Instead, you should have received a beaded liner track (referred to as a "coping bead receiver" in ***Image 22***).

b. The beaded liner track should be installed onto the pool wall all of the way around the pool. These pieces should be as close together as possible. Leaving spaces between bead tracks can cause liner problems later on.

c. Once all of the beaded liner track is on the wall, you can snap the liner bead into the beaded liner track at four random points around the pool. After that is done, and you are satisfied with how the liner is situated within the pool, you can continue snapping the remainder of the liner into place around the pool.

d. Go around the entire pool again making certain that the liner is securely snapped into the track. This is important to confirm so that the liner does not pull out while under the pressure of being filled with water.

NOTE: Some liners may fit very tightly, it is better to install uprights, top plate and rail before going onto next step. See Section 4.



22

Important Note:
Do not trim off the excess liner. (If the liner ever needs to be removed, trimming the liner will make re-installation very difficult). Instead, roll up any excess liner and tape it in place near the top of the pool wall.

5. Proceed to Section 4 - Installing the Pool Frame

Section 4

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
ASSEMBLING THE POOL FRAME

A. INSTALLATION OF THE UPRIGHTS - Round Section

1. Install the uprights

a. The wall joint is hidden behind the upright on most pools. This assures that the skimmer and skimmer return holes are not obstructed.

b. Insert the bottom of the upright onto the bottom plate. Make sure that the hooks at the bottom of the upright are inserted into the openings in the bottom bottom. ***(Image 1)***

c. There are no screws needed for this assembly.

1

Important Note:
Use the ridges in the pool wall to make sure the upright column is straight up and down.

Important Note:
Ensure to leave a gap between the two bottom rails.

See Diagram:
Please refer to your pool's footprint (Section 1, last page) for gap measurement.

B. INSTALLATION OF TOP LEDGES AND LEDGE COVERS

1. Install stabilizers

a. Install the stabilizers on the wall while ensuring to leave a gap between each end. ***(Image 2)***


2

Section 4

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
ASSEMBLING THE POOL FRAME

B. INSTALLATION OF TOP LEDGES AND LEDGE COVERS

2. Install top ledges - Round Section

a. The back ledge cover installation completes the functionality of the upright by linking together the upright, the wall and the stabilizer. Insert the back ledge cover in the upright head openings. Lock the hooks into the openings along with the screws on the top ledge. ***(Image 3)***


3

b. Place the top ledges between the uprights. The outside end of the top ledge must be inserted into the opening on top of the upright. Partially insert 1 inch screws on top. ***(Image 4)***

c. Evenly distribute the space between the top ledges to center them between the uprights.

Important Note:
Ensure to leave a gap between the two stabilizers.

See Diagram:
Please refer to your pool's footprint (Section 1, last page) for gap measurement.


4

d. Make sure to level the two axes of the uprights by pushing slightly inwards before tightening the screws permanently. ***(Image 5)***

Important Note:
We suggest that you install all the top ledges on the wall before attaching them.


5

Section 4

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
ASSEMBLING THE POOL FRAME

B. CONT. INSTALLATION OF TOP LEDGES AND LEDGE COVERS

3. Install top ledges - Straight Section

a. Secure top plates in straight section with screws. ***(Image 6)***

b. Attach the ledge cover onto the top plate and secure with the back ledge cover. ***(Image 7)***

c. Attach the top ledges. ***(Image 8)***

d. Attach top ledge finishing piece cover. ***(Image 9)***



6



7



8



9

Section 4

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
ASSEMBLING THE POOL FRAME

B. CONT. INSTALLATION OF TOP LEDGES AND LEDGE COVERS

4. Install the ledge covers-Round Section

a. Insert the 2 front hooks of the ledge cover into the upright openings. (Exterior side of the pool). ***(Image 10)***

b. Install the ledge cover from front to back by inserting the 4 ledge cover hooks into the top ledge openings. ***(Image 11)***

c. Insert the three rear tabs of the ledge cover into the molded hooks on the back side of the back of the ledge cover. ***(Images 12 & 13)***







Section 4

GENERAL INSTRUCTIONS - YARDMORE OVAL POOLS
ASSEMBLING THE POOL FRAME

D. FILL YOUR POOL WITH WATER

1. Finish filling the pool



a. Turn off the vacuum and carefully remove it from the pool.

b. Fill the pool with water to 2" (5cm) below the lowest opening. Make sure you remove any creases from the liner in the bottom of the pool before the water level gets too high.

c. While the pool is filling, remvoe the nails that were holding the bottom rails in place.

d. Your pool is now installed. You must now install the filter and pump, the skimmer and water return inlet. Please follow the installation instructions that come with these products.

Important Note:
Before making any openings in the liner, fill the pool with 60cm (24") of water to stretch the liner fully. When filling your pool, begin with a garden hose until there is about 30cm (12") of water in the pool. This will allow the liner to stretch gradually. You can then use a heavier flow to finish filling it up.

IMPORTANT:
Make sure that your pool is round, do not assume that by filling up the pool that this will help the pool to place itself into a perfect round circle. Ensure that it is round before filling up the pool with water.

IMPORTANT SAFETY INFORMATION:
Please refer to the safety page at the beginning of this instruction manual. You must follow the rules and information regarding placement of safety stickers on your pool.